



CLIENT

The Harper family
Carrer de Sant Pere, 7, 2nd floor, flat 1
08500 Vic

PROJECT

Full kitchen renovation (11 m²)
Same address
Duration: 4 weeks

Quote for the full renovation of the kitchen, based on the site visit of 15/09/2026 and the attached floor plan (page 6). Includes materials, labour and waste removal.

Summary by section

1. Strip-out and removal	€1,310.00
2. Building work and tiling	€1,960.00
3. Electrical work	€2,150.00
4. Plumbing	€928.00
5. Units and worktop	€11,682.00
6. Cleaning and finishing	€710.00
Subtotal	€18,740.00
VAT (10%)	€1,874.00
Total	€20,614.00

1 Strip-out and removal

DESCRIPTION	QTY	UNIT PRICE	AMOUNT
Removal of the existing units and appliances	1	€260.00	€260.00
Removal of the wall tiling	24 m ²	€12.00	€288.00
Removal of the existing flooring	11 m ²	€14.00	€154.00
Protection of the common areas and the flat	1	€228.00	€228.00
Rubble removal and 5 m ³ skip	1	€380.00	€380.00
Section 1 total			€1,310.00

2 Building work and tiling

DESCRIPTION	QTY	UNIT PRICE	AMOUNT
Levelling the walls with mortar	24 m ²	€11.00	€264.00
Porcelain wall tiles, laid	24 m ²	€32.00	€768.00
Porcelain floor tiles, laid	11 m ²	€36.00	€396.00
Plasterboard suspended ceiling	11 m ²	€28.00	€308.00
Emulsion paint, ceiling and walls	1	€224.00	€224.00
Section 2 total			€1,960.00

3 Electrical work

DESCRIPTION	QTY	UNIT PRICE	AMOUNT
New consumer unit with RCDs and circuit breakers	1	€640.00	€640.00
New circuits for the oven, hob and dishwasher	3	€145.00	€435.00
Lighting points and sockets	14	€52.00	€728.00
LED lighting under the wall units	1	€347.00	€347.00
Section 3 total			€2,150.00

4 Plumbing

DESCRIPTION	QTY	UNIT PRICE	AMOUNT
Hot and cold water supply (multilayer pipe)	1	€520.00	€520.00
PVC waste pipes	1	€260.00	€260.00
Dishwasher and sink connection	1	€148.00	€148.00
Section 4 total			€928.00

5 Units and worktop

DESCRIPTION	QTY	UNIT PRICE	AMOUNT
Base units, matt laminate	8	€420.00	€3,360.00
Wall units, matt laminate	4	€310.00	€1,240.00
Tall unit for oven and fridge	1	€1,150.00	€1,150.00
Stainless steel sink and tap	1	€590.00	€590.00
Fitting the units	1	€1,560.00	€1,560.00
Quartz worktop, 20 mm	6.2 m	€610.00	€3,782.00
Section 5 total			€11,682.00

6 Cleaning and finishing

DESCRIPTION	QTY	UNIT PRICE	AMOUNT
Final builders' clean	1	€290.00	€290.00
Rubble removal	1	€420.00	€420.00
Section 6 total			€710.00

Terms

- **Payment:** 50% on signing this quote and 50% on completion.
- **Unforeseen work:** any work not included in this quote will be invoiced separately.
- **Validity:** 30 days from the date of this quote.
- **Guarantee:** 2 years on labour; materials as per the manufacturer's warranty.

Client's signature

Ribera Renovations S.L.

